TITLE:

# WBS Development for EPC Projects

Athor:

**Behzad Mousavi, MSc in Industrial Engineering**
**Planning & Project Control Specialist**

### System-Based Approach

Unlike construction's area-based WBS, commissioning is best structured by **system** (e.g., Cooling Water System, Nitrogen System) because systems span multiple areas and must be tested as integrated units.

---

## Common WBS Mistakes in EPC Projects

Avoiding these pitfalls separates average WBS from world-class WBS.

### Top 10 WBS Mistakes

| # | Mistake | Consequence | Solution |
|---|---------|-------------|----------|
| 1 | **Activity-based WBS** | Progress measurement impossible | Use deliverable-oriented elements |
| 2 | **Over-decomposition** | WBS becomes unmanageable | Limit to 5 levels; stop at work package |
| 3 | **Under-decomposition** | Poor cost control | Ensure work packages are 80–2,000 man-hours |
| 4 | **Inconsistent coding** | Reporting chaos | Standardize in PEP; enforce via tool |
| 5 | **No WBS Dictionary** | Scope ambiguity | Develop dictionary with every WBS release |
| 6 | **OBS/CBS mismatch** | EVM failure | Build integration matrix at WBS creation |
| 7 | **Ignoring change management** | Scope creep | Formal change control process |
| 8 | **Overlapping elements** | Double-counting in EVM | Peer review WBS with 100% rule check |
| 9 | **Missing interfaces** | Schedule gaps | Add explicit interface WBS elements |
| 10 | **Stakeholder exclusion** | Rejection | Conduct WBS workshops with all parties |

### Red Flags

- More than **8,000 WBS elements** in a typical EPC project (overkill)

- Less than **500 WBS elements** in a $100M+ project (underdeveloped)

- **No baseline** saved in Primavera P6 after WBS approval

- **Different WBS** between engineering and construction teams

---

## WBS Standards and Frameworks

Professional WBS development must comply with recognized standards to ensure credibility, defensibility, and contractual alignment.

### AACE International Recommended Practices

- **RP 29R-03:** Forensic Schedule Analysis (references WBS)

- **RP 37R-06:** Cost Estimate Classification (aligns with WBS maturity)

- **RP 52R-06:** EVM in Engineering & Construction

- **RP 10R-97:** Cost Engineering Terminology

AACE emphasizes that WBS maturity should progress with project phases:

| Project Phase | WBS Maturity |
|---------------|--------------|
| Pre-FEED | Level 2 only (conceptual) |
| FEED | Levels 1–3 defined |
| Detailed Engineering | Levels 1–5 fully developed |
| Construction | Levels 1–5 with work packages active |

### PMI PMBOK (7th Edition)

- Defines WBS as a **"deliverable-oriented hierarchical decomposition"**

- Emphasizes the **100% rule** as the single most important principle

- Requires **WBS Dictionary** as a mandatory project document

### ISO 21500 & ISO 21502

- Provide international guidance on WBS

- Emphasize **stakeholder alignment** during WBS development

- Recognize industry-specific variations

### Industry-Specific Standards

- **Aramco SAEP-302:** WBS requirements for Saudi Aramco projects

- **Shell DEP:** WBS standards for Shell projects

- **ADNOC:** WBS coding requirements

- **FIDIC Contracts:** Scope definition via WBS

---

## WBS Governance and Change Control

A WBS is not a one-time deliverable—it is a **living framework** requiring disciplined governance.

### WBS Approval Workflow

1. **Draft WBS** – Project Controls team

2. **Stakeholder Review** – Engineering, Procurement, Construction leads

3. **Client Approval** – Formal sign-off with contract implications

4. **Baseline Freeze** – WBS baseline saved in Primavera P6

5. **Controlled Updates** – Only via formal change control

### Change Control Process

Any WBS modification must follow:

1. **Change Request** – Documented scope change

2. **Impact Assessment** – Cost, schedule, risk implications

3. **Approval** – Change Control Board (CCB)

4. **Baseline Update** – New baseline revision (Rev A, Rev B)

5. **Communication** – Distributed to all stakeholders

### Version Control

Maintain a **WBS revision log** with:

- Revision number and date

- Approving authority

- Scope changes included

- Affected documents

- Baseline impact

---

## Tools for WBS Development

### Primavera P6 EPPM

- **Native WBS module** with unlimited hierarchical levels

- **WBS-level budgeting** and earned value rollup

- **Integration with schedules**, resources, and costs

- **WBS baselines** for variance analysis

### Microsoft Project

- **Outline Number** feature for WBS coding

- **Custom fields** for WBS Dictionary

- **Limitations:** Less robust than P6 for mega-projects

### Dedicated WBS Tools

- **WBS Director** – Specialized WBS modeling

- **Safran Project** – Integrated project controls suite

- **Deltek Acumen** – Schedule diagnostics with WBS checks

### Complementary Tools

- **Microsoft Visio** – WBS diagramming

- **Excel** – WBS Dictionary management

- **Power BI** – WBS-level dashboards

---

## FAQ

### Q1: How many WBS levels should an EPC project have?

Typically **3 to 5 levels** is optimal. Level 1 is the project, Level 2 is major phases, Levels 3–4 are systems/areas/disciplines, and Level 5 contains work packages. Going beyond 5 levels creates administrative overhead without analytical benefit.

### Q2: Should the WBS be the same for engineering and construction?

No. Engineering WBS is typically **discipline and deliverable-based** (e.g., piping, electrical), while construction WBS is **area-based** (e.g., Unit 100, Unit 200). However, both must integrate at Level 2 (Project Phases) to maintain alignment.

### Q3: How do I measure progress against a WBS element?

Use **physical percent complete** tied to measurable deliverables. For engineering, use milestone weighting. For construction, use physical units (tons, meters, cubic meters). Avoid "time elapsed" or subjective estimates.

### Q4: What is the relationship between WBS and CBS?

The **Cost Breakdown Structure (CBS)** maps to the WBS to enable cost allocation. A single WBS element can map to multiple CBS elements (labor, material, equipment), but each CBS element must trace back to one WBS element.

### Q5: Can I reuse a WBS from a previous EPC project?

Yes, but with caution. **WBS templates** from similar projects are excellent starting points. However, every project has unique scope, site conditions, and contractual requirements that must be reflected. Always conduct a scope validation workshop.

### Q6: How often should I update the WBS?

The WBS should be **baseline-frozen** after approval. Updates occur only through formal **change control**. Uncontrolled WBS changes destroy baseline integrity and invalidate earned value analysis.

### Q7: Who is responsible for WBS development?

The **Project Controls Manager** typically leads WBS development, with input from Engineering, Procurement, and Construction leads. Final approval requires the **Project Manager** and often the **client representative**.

### Q8: How does WBS support claims and disputes?

A well-documented WBS with a controlled revision history provides **defensible evidence** of scope, deliverables, and contractual obligations. This is critical for defending or pursuing claims in delay and cost disputes.

### Q9: What is a WBS element vs. an activity?

A **WBS element** represents a deliverable or scope of work. An **activity** is the task performed to produce that deliverable. Multiple activities roll up to one WBS element. Never confuse the two.

### Q10: How do I handle cross-project WBS alignment in a program?

For programs with multiple EPC projects, establish a **program-level WBS** at Level 1, with each project as a Level 2 element. Each project then develops its own detailed WBS beneath its assigned node.

---

## Conclusion

**WBS development for EPC projects** is both a science and an art. It demands technical precision to decompose complex scope, stakeholder wisdom to align competing perspectives, and disciplined governance to maintain integrity throughout the project lifecycle.

A well-crafted WBS delivers exponential value:

- ✅ **Scope clarity** across engineering, procurement, and construction

- ✅ **Integrated cost, schedule, and risk management**

- ✅ **Accurate earned value measurement**

- ✅ **Defensible claims position**

- ✅ **Stakeholder alignment** from boardroom to construction site

The investment of time in WBS development—typically 2–4 weeks during project setup—pays dividends throughout years of project execution. As the old project controls adage goes: *"A project without a WBS is just a list of tasks hoping for the best."*

> **Next Step:** Download this guide, run a WBS health check against the 10 common mistakes checklist, and schedule a WBS alignment workshop with your EPC project team this week.

**---**

***Last Updated: August 2026***

***Author: Behzad Mousavi | Planning & Project Control Manager***

***Category: Project Controls, EPC Planning, WBS Development***

**---**

**> **Suggested Internal Links:****

**> - Primavera P6 Scheduling Best Practices**

**> - EPC Project Delay Due to 10 Critical Schedule Risks**

**> - Earned Value Management in Primavera P6: A Step-by-Step Guide**

**> - Critical Path Method (CPM) in EPC Projects**

**> **Suggested Tags/Keywords:****

**> WBS development, EPC projects, work breakdown structure, project controls, AACE, PMI, Primavera P6, engineering procurement construction, deliverable-oriented WBS, WBS dictionary, CBS, OBS, RBS, earned value management, mega-projects, oil and gas, power plants, construction planning**

**For more technical articles, training materials, and professional resources, visit our page in GitHub as a link below:**

- [https://sbmousavices.github.io/industrial-Tools](https://sbmousavices.github.io/industrial-Tools)

---